

## BILL OF MATERIALS

Project: Repair, Renovation and Maintenance of City Prosecution Office of Iriga, including Labor and Materials

All works to be undertaken shall be in accordance with the scope of work. It includes the design, labor, materials, equipment and furnishing of all materials with supervision necessary for the complete construction of the said project, so that what is mentioned or shown on one, although not mentioned or shown in another, shall be considered as appearing in both.

A.1. Concrete Works with the use of the following materials including, but not limited to:

4 pcs.	2 ½" DIA. G.I Pipe (S-40)
25 bags	Cement
2 cu.m	Sand
2 cu.m.	Gravel
6 pcs.	12mm Ø X 6.0m RSB
12 pcs.	10mm Ø X 6.0m RSB
2 kg.	#16 G.I. Tie Wire
2 pcs.	4" Cut-off Disc

A.2. Forms and Scaffolding Works with the use of the following materials including, but not limited

to:

8 pcs.	2" x 3" x 12' Coco lumber
8 pcs.	2" x 2" x 12' Coco lumber
2 pcs.	¼" x 4' x 8' Plywood
2 kg.	4" Common Wire Nail
2 kg.	3" Common Wire Nail
2 kg.	1 1/2" Common Wire Nail

A.3. Wall Works with the use of the following materials including, but not limited to:

18 pcs.	2" x 2" x 12" Good Lumber
8 pcs.	¼" x 4' x 8' Marine Plywood
3 kg.	3" Concrete Nail
3 kg.	4" Common Wire Nail
3 kg.	3" Common Wire Nail
3 kg.	2" Common Wire Nail
5 kg.	1 ½" Common Wire Nail

A.4. Roofing Works with the use of the following materials including, but not limited to:

3 pcs.	1.2mm x 2" x 4" C-Purlins
6 pcs.	1.2mm x 2" x 3" C-Purlins
8 pcs.	#26 x 12' Corrugated G.I Sheet
6 pcs.	#26 Flashing
2 pcs.	#26 Gutter
2 kg.	Welding Rod
2 pcs.	4" Ø Cut-off Disc
2 box	3/16" Blind Rivets
500 pcs.	Toxscrew
1 gal.	Roof Guard
1 gal.	Epoxy Red Oxide Primer
1 gal.	Quick Dry Enamel
1 gal.	Paint thinner
1 lit.	Vulcaseal

A.5. Plumbing Works with the use of the following materials including, but not limited to:

- 1 pc. 1" DIA. PPR Pipe (Plain)
- 2 pcs. 1" DIA. PPR Elbow 90° (threaded)
- 2 pcs. 2" DIA. PVC Pipe
- 1 pc. 2" DIA. PVC P-Trap
- 3 pcs. 2" DIA. PVC Elbow 90°
- 1 pc. Faucet
- 1 pc. Kitchen Sink
- 2 pcs. Teflon tape
- 1 can 400cc Solvent Cement

A.6. Doors and Windows Works with the use of the following materials including, but not limited to:

- 2 set 0.80m x 2.10m Panel Door with Header and Jamb
- 2 set 1.20m x 1.20m Steel Casement Window with Glass
- 2 pcs. Door Knob

A.7. Electrical Works with the use of the following materials including, but not limited to:

- 10 pcs. 4" x 4" Junction Box
- 5 pcs. Utility Box
- 8 pcs. Electrical tape
- 1 box 3.5mm<sup>2</sup> THHN Wire (100mts)
- 4 sets 40W Twin Fluorescent Lamp
- 6 sets Pinlight
- 1 set 1 Gang Switch
- 5 sets Convenient Outlet
- Set ACU Convenient Outlet
- 1 roll ¾" Moldflex Pipe
- 4 kg. #16 G.I Tie Wire

A.8. Painting Works with the use of the following materials including, but not limited to:

- 2 gals. Flat Latex Paint
- 2 gals. Flat Wall Enamel
- 2 gals. Semi-gloss Latex
- 2 gals. Quick Dry Enamel
- 1 gal. Paint thinner
- 1 gal. Glazing Putty
- 1 gal. Masonry Putty
- 4 pcs. Square Putty Knife
- 15 pcs. Mesh Tape
- 3 sets Roller Brush with tray
- 3 pcs. Baby Roller
- 3 pcs. 4" Paint brush
- 3 pcs. 2" Paint Brush

A.9. Floor Furnishing Works with the use of the following materials including, but not limited to:

- 380 pcs. 0.30 x 0.30m Vinyl Floor Tile
- 1 gal. Rugby glue